

Subject: Re: PROPOSAL (new) SOLUGH WALL

From: Fred Sutton <fred.sutton@lacity.org>

Date: 06/04/2015 10:43 AM

To: Donald Duckworth <duckworth.donald@gmail.com>

CC: John Ruhlen <jruhlen916@aol.com>, Miki Payne2 <miki@hbdrollinger.com>

Thank you Don. I will speak with Councilman tomorrow in regards to this estimate and see where we are at. Thank you.

Kind regards,



Logo5-web.

Frederick Sutton

Field Deputy: Westchester, Playa Del Rey & Playa Vista

Councilmember Mike Bonin

City of Los Angeles

[310-568-8772](tel:310-568-8772) | www.11thdistrict.com



[Sign Up for Mike's Email Updates](#)

Download the City of Los Angeles MyLA311 app for smartphones!



Android



Download

MyLA311 links Angelenos with the services and information they need to enjoy their city, beautify their community and stay connected with their local government. With MyLA311, City of Los Angeles information and services are just a few taps away.

On Thu, Jun 4, 2015 at 6:08 AM, Donald Duckworth

<duckworth.donald@gmail.com> wrote:

Good Morning Fred...

I forgot all about this last week! Here is the east side (SRS) slough wall proposal. Adding a reasonable contingency, because there will be costs that were not anticipated, this contractor's cost should be considered to be \$12,000.00.

What's the next step here?

Thanks for your help.

----- Forwarded message -----

From: <DERRYLDENNE@aol.com>

Date: Tue, Mar 24, 2015 at 11:22 AM

Subject: PROPOSAL (new) SOLUGH WALL

To: duckworth.donald@gmail.com

**D. D. CONSTRUCTION
DERRYL DENNE
8335 Somerset Blvd
Paramount, CA 90723
(562) 569-2708**

Date: 03/24/15

PROPOSAL UP TO DATE

To:
Don Duckworth

Job Location:
Sepulveda Blvd
79th & 83rd East Side
Westchester

WORK TO BE DONE

**BUILD CONCRETE SLOUGH WALL
OR CURB & MOVE SPRINKLERS**

POUR 469 LF OF SLOUGH WALL OR CURB.

- 1). FORM AND POUR (23) SECTIONS OF CONCRETE WALL
TO PREVENT DIRT & MUD RUN OFF ON TO SIDEWALK.
6" X 24" X 569' (LF CURB)**
 - * THERE ARE (13) AREAS BEHIND TREES @ (8 LF) EACH**
 - * THERE ARE (2) AREAS IN FRONT OF TREES @ (8 LF) EA.**
 - * THERE ARE (8) OTHER AREAS 13' 13' 15' 165' 13' 77' 39' 14'**

TOTAL OF 469 LF.....

**NOTE : THE (13) AREAS BEHIND TREES WILL NEED TO HAVE
A DEEPER FOOTING BECAUSE IN MIDDLE OF SLOPE.**

MOVE SPRINKLERS BEHIND SLOUGH WALL OR CURB.

- 2). DIG UP EXISTING SPRINKLERS & REROUTE BEHIND WALL**
 - * MAY NEED TO CHANGE OUT SPRINKLER HEADS AS THEY
ARE MANY DIFFERENT KINDS ON THERE NOW..**

TOTAL MATERIALS AND LABOR.....\$ 10,669.75

***Thank You For The Opportunity
To Give You This Proposal.***

---- Derryl ---